Oakmere Building Co.

Builders & landscapers - Colchester, Essex
Unit 4, Example Business Park, Colchester CO1 0XX · 01206 000 000 · quotes@oakmere-demo.co.uk

QUOTATION

OAK-261019-A960

QUOTE FOR	DATE	VALID UNTIL
Customer	19 Oct 2026	18 Nov 2026

YOUR REQUEST

"We're doing up the lounge (5m by 4m): paint the walls with two coats and re-skim the ceiling, about 20 sqm. Plus laminate flooring in the bedroom, 4 x 3.5 m."

1. Painting – 43.2 m^2, 2 coats

Description	Qty	Unit	Unit price	Amount
Trade emulsion (5L) (2 coats @ 12 m^2/L)	2	tin	£52.90	£105.80
Filler, tape, sheets & sundries	44	m^2	£0.69	£30.36
Decorator	2	day	£200.00	£400.00
			Subtotal	**£536.16**

- 43.2 m^2 of walls/ceilings, 2 coats of emulsion; furniture moved by customer.
- Walls of a 5 x 4m room with 2.4m ceilings

2. Plastering (skim) – 20 m^2

Description	Qty	Unit	Unit price	Amount
Multi-finish plaster (25kg) (~10 m^2 per bag)	3	bag	£15.53	£46.59
PVA bonding agent (5L)	1	tub	£20.70	£20.70
Beading, scrim tape & sundries	20	m^2	£1.38	£27.60
Plasterer	1	day	£220.00	£220.00
			Subtotal	**£314.89**

- Skim coat over sound plasterboard/backing, 20 m^2.

3. Laminate flooring – 14 m^2

Description	Qty	Unit	Unit price	Amount
Laminate flooring (2.2m^2 pack) (incl. 10% waste)	7	pack	£50.60	£354.20
Flooring underlay	15	m^2	£4.83	£72.45
Scotia, thresholds & trims	14	m^2	£1.84	£25.76
Floor Fitter	1	day	£220.00	£220.00
			Subtotal	**£672.41**

- 14 m^2 over a level, dry subfloor; old flooring removal not included.

Works total	£1,523.46
Contingency (5%)	£76.17
Total (ex. VAT)	£1,599.63
VAT (20%)	£319.93
TOTAL	**£1,919.56**

Terms. This quotation is valid until 18 Nov 2026. Prices are based on the measurements and assumptions listed above and are subject to a site survey. A 25% deposit secures your start date; the balance is due on completion. Any variations will be agreed in writing before work starts.